

केन्द्रीय रेशम उत्पादन अनुसंधान एवं प्रशिक्षण संस्थान

Central Sericultural Research & Training Institute

[केन्द्रीय रेशम बोर्ड -
वस्त्र मंत्रालय - भारत सरकार]
मानंदवाडी रोड, श्रीरामपुरा,



[Central Silk Board -
Min. Of Textiles - Govt. of India]
Manandavadi Road, Srirampura

Mysore - 570 008

मैसूर - 570 008

Date: 10.03.2026

No. CSB/RTI/ROB/SEEM/98/19-20/Maint/80

To,
M/s

Sirs,

Sub: Inviting sealed quotations for providing false Ceiling work and Lightings to false Ceiling to Museum in CSRTI, Mysore - reg.

=x=x=x=x=x=

It is to inform that providing false Ceiling work and Lightings to false Ceiling to Museum by undertaking various improvement works of this Institute. Hence, sealed quotations are invited from the reputed PWO Contractor/Licensed/Registered/GST holder suppliers/agencies to submit their lowest rate as per specification detailed below:-

Sl No	Descriptions of goods area and Specifications	Price / sqft	Particular amount in Rs.	Total Amount	Remark
01.	Providing and fixing in position 12mm thick plaster of parts (Gypsum anhydrous) for ceiling reinforced with hessian cloth flat surface with ceiling tiles p to a height of 5m above floor level over aluminium strips 25mm * 6mm and rendered smooth with plaster of paris including cost of materials, labour, curing complete as per specifications. Item no 7.31				
02.	Extra forsunk or raised mouldings in te plaster of Paris (Gypsum anhydrous) ceiling. Item no 7.29				
03.	Supplying of recess mounting non integrated type LED down light... W luminaire comprising of pressure decast/ extruded aluminium housing, with springloaded false Ceiling clamps, LED of Power/COB with CCT6500 degreeK, CRI>70%. Efficacy>100 lumenperW, 120 degree beamsread, life>25000 burning hoursand Compliance toIS10322/IEC60598,LM79&LM80. The lamp compartment is enclosed with antiglare opal diffuser which enhances the lighting level. LED"saredriven by HF electronic driver integrated in a separate control gearassembly, with PF>0.95, powerloss should<5% of lamp				


	<p>Wage, short circuit and open circuit protect into be integrated in the circuit, THD less than 20% , Life as per LM79. The operating input voltage should be between 130 to 275V. Bs Approved and Tested by NABL/CPRI accredited laboratory with 2 years Warranty against any manufacturing defect working under standard electrical condition. 56W.(Item No. 11.4.1) Vol-6</p>				
04.	<p>Supplying & fixing-flexible LED Strip Light... WPower consumption in 5ms lngth CCT6500 degree K, CRI>70%. Efficacy>80 lumenperW,life>25000burning hoursand compliance to IS10322/IEC60598, IM79 & LM80. The LED are driven by HF electronic driven non integrated, with PF>0.95, power loss should<5% of lamp Wage., short circuit and open circuit protection to be integrated in the circuit,n THD less than 20%, Life as per LM79. The operating inpt voltage should be between 130 to 275V. BIS Approved with 2 years Warranty against any manufacturing defect working under standard electrical condition.(Item No. 11.1) Vol-6</p>				
05.	<p>Supplying of recess mounting non integral type..... LEDw luminaire comprising of pressured cast/ extruded aluminium housing, wuithspring loaded false ceiling clamps, powerLEDs with CCT6500 degree, CRI>70%. Efficacy>100 limen perW, 120degree beam spread, life>2500 burning hours and Co,pliance to IS10322/IE C60598, LM79 & LM80. The lamp compartment is enclosed wit anti glareopal diffuser which enhances the lighting level LEDs are driven by HF electronic driver integraed in a separate control gear assembl., with PF>0.95, power loss should< 5% of Lamp Wage ., short circuit and open circuit protection to be integrated in the circuit, THD less than 20% ,</p>				

<p>Life as per LM79. The operating input voltage should be between 130 to 275V. BIS Approved and Tested by NABL/CPRI accredited laboratory with 2 years Warranty against any manufacturing defect working under standard electrical condition. LED modular down light 2'x2' 36W. (Item No. 11.6.3) Vol-6</p>				
--	--	--	--	--

TERMS AND CONDITION	
1	The sealed quotations to be addressed to the Director, CSR&TI, Mysore and on the cover it should be super scribed that "PROVIDING FALSE CEILING WORK AND LIGHTINGS TO FALSE CEILING TO MUSEUM" with last date 02.04.2026 at 01.00 PM for submission of quotation and 02.04.26 date of opening of quotation. 2-0300 PM
4	EMD NA (Not applicable)/will not carry any interest.
5	EXEMPTION FROM EMD NA (Not applicable)
6	VALIDITY The rate quoted should be valid for a period of 180 days from the date of opening of the quotations
7	DELIVERY SCHEDULE F.O.R. CSRTI, MYSORE
8	PAYMENT SCHEDULE Payment will be effected only after satisfactory supply and its installation of item in good working conditions
9	TAXES/OTHER STATUTORY PAYMENTS Should be quoted separately and DUTIES in percentage wherever applicable
10	WARRANTY Should be indicated
11	The materials/repair supplied shall be in conformity with specifications.
12 13	The undersigned is right and reserve to accept or reject any quotation and the process in any time The scope of work mentioned above is tentative. Contractors are advised to visit the site between 10:00 AM to 4:00 PM on working days at their own cost and obtain necessary information for preparing the quotation (location, quantum and nature of work, etc.). Payment will be made as per actual measurement and certification by the indenter/concerned officer. Concerned contractor will be responsible for actual measurement of the area & quote their rate accordingly, If any discrepancy is there in measurement they may mentioned in remarks column

You are requested to furnish your spot quotation addressed to the Director, CSRTI, Central Silk Board, Govt. of India, Srirampura, Manandavadi Road, Mysore 570 008.

Yours faithfully,


DIRECTOR

Copy to: DD Computer, CSRTI, Mysore for uploading website & CPP portal